

**3 REFLECTED CEILING AND LIGHTING PLAN**  
SCALE: 1/4" = 1'

### CEILING & LIGHTING LEGEND

2' X 2' DROP CEILING WITH WHITE SPLINES.  
OPTIONAL PAINTED CEILING TILE AND SPLINE COLORS (SPLINES MUST BE PAINTED THE SAME COLOR AS TILES):  
BLONDE PAINT (SHERWIN WILLIAMS #SW 6128) \*CUSTOMER AREA ONLY\*  
WHEAT GRASS PAINT (SHERWIN WILLIAMS #SW 6408) \*CUSTOMER AREA ONLY\*

SYMBOL	DESCRIPTION	MANUF.	SUPPLY	QTY	NO.	NOTES
[Symbol]	2'x2' RECESSED FLUORESCENT FIXTURE	LIGHTLITER	SPECIALTY STORE LIGHTING	DAI	10	RECESSED FLUORESCENT FIXTURE (SPS25VA8P120S3). USES (2) PL-L40W/35/RS BIA2 2G11 LIGHT BULBS.
[Symbol]	2'x2' RECESSED FLUORESCENT FIXTURE W/PARABOLIC LENS	LIGHTLITER	SPECIALTY STORE LIGHTING	DAI	12	RECESSED FLUORESCENT FIXTURE W/PARABOLIC LENS (CPA29LS2FT120S3). USES (2) PL-L40W/35/RS BIA2 2G11 LIGHT BULBS.
[Symbol]	4' FLUORESCENT STRIP LIGHT	NON LIGHTING	SPECIALTY STORE LIGHTING	DAI	4	MODEL # MLS-28 (2) FITS BULK UP TO 10 MILS FIXTURES MAY BE CONNECTED TOGETHER ON A SINGLE 120V POWER CORD FEED. MOUNT ON 4" SHELF 87-6" AFF. & FINISH W/ 1/2" CROWN MOLDING TO CONCEAL FIXTURES. STAIN SHELF AND CROWN MOLDING W/ TWO COATS MINWAX #235 CHERRY AND POLYURETHANE WITH MINWAX FAST DRYING SATIN. SEE BACK-UP PAGE 1 OF 4 FOR DETAILS.
[Symbol]	3' FLUORESCENT STRIP LIGHT	NON LIGHTING	SPECIALTY STORE LIGHTING	DAI	4	MODEL # MLS-28 (2) FITS BULK UP TO 10 MILS FIXTURES MAY BE CONNECTED TOGETHER ON A SINGLE 120V POWER CORD FEED. MOUNT ON 4" SHELF 87-6" AFF. & FINISH W/ 1/2" CROWN MOLDING TO CONCEAL FIXTURES. STAIN SHELF AND CROWN MOLDING W/ TWO COATS MINWAX #235 CHERRY AND POLYURETHANE WITH MINWAX FAST DRYING SATIN. SEE BACK-UP PAGE 1 OF 4 FOR DETAILS.
[Symbol]	VINYL DROP-IN	G.C.	G.C.	AS REQ'D		2' X 2' DROP-IN PANEL
[Symbol]	ACOUSTICAL DROP-IN	G.C.	G.C.	AS REQ'D		2' X 2' DROP-IN PANEL
[Symbol]	2' X 2' SURFACE MOUNTED LIGHT FIXTURE WITH SEPARATE EXHAUST FAN	G.C.	G.C.	1	STANDARD SURFACE MOUNTED FIXTURE WITH ENERGY SAVING BALLAST AND 40 WATT COOL WHITE TUBES. SEPARATE EXHAUST FAN WITH A 100 CFM AIR EXCHANGE REQUIRED.	
[Symbol]	AMBER PENDANT LIGHT (LARGE)	TRUE TO FORM	SPECIALTY STORE LIGHTING	DAI	9	LARGE SUSPENDED PENDANT FIXTURE (SV5410-PL). USES (1) 15W FLUO LAMP (MAXLITE ML55EA). PENDANT LIGHTS ARE PLACED AROUND THE PERIMETER OF THE RESTAURANT AND SHOULD BE INSTALLED AT A HEIGHT OF 6'-6" (196.1cm) FROM THE FLOOR TO THE BOTTOM OF THE FIXTURE. (A PENDANT STEM KIT IS AVAILABLE THROUGH SPECIALTY STORE LIGHTING FOR USE WITH HIGH CEILING). RECOMMEND INSTALLING CUSTOMER SEATING BEFORE PENDANT LIGHTS TO ALLOW PRECISE PLACEMENT OF FIXTURES OVER TABLE TOPS.
[Symbol]	CEILING FAN	VILLA LIGHTING	DAI	DAI	3	MX2-AS/52CR REGENCY MX-EXCEL WITH 5 CHERRY FINISH BLADES. CAN BE INSTALLED AS DROP STYLE (WITH 6" DR 2" STEM) OR HUGGER (FLUSH) STYLE.

### FLOOR FINISH LEGEND - TUSCANY II DECOR (RANDOM PATTERN)

TILE	NO.	AREA OF STORE	MANUFACTURER	SUPPLIER	INST.	SQ/FT	DESCRIPTION
[Symbol]	1	CUSTOMER AREA	CROSSVILLE	G.C.	G.C.	265	COLORBLX STONE SERIES) 12" X 12" A1156 WHEAT COLORBLX STONE SERIES) 12" X 12" A1154 GREEN COLORBLX STONE SERIES) 12" X 12" A1153 CLAY WHEN INSTALLING THE RANDOM PATTERN, THE PERCENTAGES OF THE ABOVE COLORS ARE AS FOLLOWS: WHEAT - 80% GREEN - 12% CLAY - 8%. (THE GREEN AND CLAY SHOULD BE DISTRIBUTED EVENLY, BUT RANDOMLY THROUGHOUT AS NOT TO REPRESENT A NOTICEABLE PATTERN). USE DARK GREY DR DARK BROWN GROUT THROUGHOUT ENTIRE CUSTOMER AREA.
[Symbol]	2	PUBLIC ACCESSIBLE RESTROOM	CROSSVILLE	G.C.	G.C.	N/A	COLORBLX STONE SERIES) 12" X 12" A1156 WHEAT WITH DARK GREY DR DARK BROWN GROUT.
[Symbol]	3	SERVICE/BACKROOM AREA	CROSSVILLE	G.C.	G.C.	208	COLORBLX STONE SERIES) 12" X 12" A1156 WHEAT WITH DARK GREY DR DARK BROWN GROUT.

**WALL BASE**  
NOTE: WALL BASE OPTION MUST MATCH FLOOR OPTION LISTED ABOVE IN ALL AREAS OF STORE

SYMBOL	DESCRIPTION	MANUFACTURER	SUPPLIER	INST.	NOTES
[Symbol]	6" X 12" COVE BASE OR 4" X 12" BULLNOSE	CROSSVILLE	G.C.	G.C.	COLORBLX STONE SERIES A1156 WHEAT WITH DARK GREY DR DARK BROWN GROUT. WITH A MINIMUM 3/8 INCH RADIUS

**ADDITIONAL COMMENTS:**  
1.) FLOORING CONTRACTOR IS RESPONSIBLE FOR OWN DETERMINATIONS ON SUBFLOOR REQUIREMENTS AND TO INSTALL IN ACCORDANCE WITH CODE REQUIREMENTS AND TO INDUSTRY AND MANUFACTURER SPECIFICATIONS.  
2.) THE SQUARE FOOTAGE CALCULATIONS OF THE FLOORING MUST BE VERIFIED BY THE G.C. AND FRANCHISE OWNER. SUBWAY STORE DESIGN DEPARTMENT WILL NOT ACCEPT RESPONSIBILITY FOR ANY INACCURACIES.  
3.) BULLNOSE WALL BASE IS TO BE INSTALLED ON TOP OF THE TUSCAN STUCCO WALL COVERING. 1"-3" OF TUSCAN STUCCO WALL COVERING IS RECOMMENDED TO BE COVERED TO PROVIDE A TIGHT FIT.

**FLOOR TILE KEY**

- COLORBLX SERIES) 12" X 12" A1156 WHEAT
- COLORBLX SERIES) 12" X 12" A1154 GREEN
- COLORBLX SERIES) 12" X 12" A1153 CLAY

**RANDOM FLOOR TILE PLACEMENT EXAMPLE**

### WALL FINISH LEGEND (TUSCANY II DECOR)

\*SEE TUSCANY II BACK-UP SHEET 1 OF 4 AND 2 OF 4 FOR PROPER INSTALLATION OF WALLFINISHES IN CUSTOMER AND SERVICE AREAS. (SEE TUSCANY II SUPPLEMENTAL TILE BACK-UP SHEET WHEN APPLICABLE)

SYMBOL	DESCRIPTION	MANUFACTURER	SUPPLY	INST.	NOTES
[Symbol]	SUBWAY MURAL	SINGLO FABRICS	D.A.I.	G.C.	VINYL WALLCOVERING/UPPER CORNER MOLDING AND GROUT OR BUTTERNUT BRICK WALLCOVERING AS REQUIRED
[Symbol]	TUSCAN STUCCO WALLCOVERING	SINGLO FABRICS	D.A.I.	G.C.	VINYL WALLCOVERING WITH LOWER CHAIR RAIL MOLDING
[Symbol]	WINDOW FRAME	G.C.	G.C.	G.C.	PAINT SHERWIN WILLIAMS #SW6356 COPPER MOUNTAIN.
[Symbol]	TUSCAN STUCCO WALLCOVERING	SINGLO FABRICS	D.A.I.	G.C.	VINYL WALLCOVERING/UPPER CORNER MOLDING AND GROUT OR BUTTERNUT BRICK WALLCOVERING AS REQUIRED
[Symbol]	RED WALL COVERING	SINGLO FABRICS	D.A.I.	G.C.	VINYL WALLCOVERING WITH LOWER CHAIR RAIL MOLDING AS REQUIRED
[Symbol]	TUSCAN STUCCO WALLCOVERING	SINGLO FABRICS	D.A.I.	G.C.	VINYL WALLCOVERING WITH LOWER CHAIR RAIL MOLDING
[Symbol]	CABINET/WALL LAMINATE	WILSONART	G.C.	G.C.	FOINT-HILL PEAR (#10745-60)- INSTALL GRAIN HORIZONTALLY
[Symbol]	WALL CAPS	G.C.	G.C.	G.C.	HARDWOOD PLANK (STAINED MINWAX #235 CHERRY AND POLYURETHANE WITH MINWAX FAST DRYING CLEAR SATIN)
[Symbol]	FRP DR PAINTED WALLS	MARLITE/GC	DAI/GC	G.C.	WHITE FRP PANELS OR OFF-WHITE SEMI-GLOSS PAINT
[Symbol]	FIBERGLASS REINFORCED POLYESTER PANELS (FRP)	MARLITE	D.A.I.	G.C.	FRP PANELS WATER RESISTANT COVERING. WHITE OR #ALMOND (ALMOND OPTION ONLY IF PERMITTED BY HEALTH/BUILDING CODE)
[Symbol]	RESTROOM TILED WALLS	CROSSVILLE/DAL-TILE	G.C.	G.C.	OPTION 1) COLORBLX STONE FLOOR TILE MOUNTED FLOOR TO CEILING. CHOOSE 1 OR MORE OF THE FOLLOWING: A1153 CLAY, A154 GREEN, A156 WHEAT. OPTION 2) DAL-TILE K165 ALMOND 4 1/4" X 4 1/4" CERAMIC TILE FLOOR TO CEILING.
[Symbol]	MOSAIC TILE (RIGHT)	IMAGINE TILE	D.A.I.	G.C.	4 1/4" X 4 1/4" CERAMIC TILE. VEGETABLE GRAPHIC TILES FRAMED BY 1/4" LIGHT CHERRY. SEE TUSCANY II SUPPLEMENTAL TILE BACK-UP SHEET FOR INSTALLATION.
[Symbol]	MOSAIC TILE (LEFT)	IMAGINE TILE	D.A.I.	G.C.	4 1/4" X 4 1/4" CERAMIC TILE. VEGETABLE GRAPHIC TILES FRAMED BY 1/4" LIGHT CHERRY. SEE TUSCANY II SUPPLEMENTAL TILE BACK-UP SHEET FOR INSTALLATION.
[Symbol]	CERAMIC TILE	IMAGINE TILE	G.C.	G.C.	4 1/4" X 4 1/4" CERAMIC TILE. COLOR 1A (LIGHT CHERRY). SEE TUSCANY II SUPPLEMENTAL TILE BACK-UP SHEET FOR INSTALLATION.
[Symbol]	GRIMALDI CERAMIC TILE RESTROOM/SERVICE AREAS	ASSOCIATED INC/INTERMOUNT LTD	G.C.	G.C.	8" X 8" CERAMIC TILE. COLOR: CURRY (YELLOW). ITEM# C212005061. 8" X 8" CERAMIC TILE. COLOR: MUSGO (GREEN). ITEM# C212005051. GROUT COLOR: #17 BUTTER CREAM NON SANDED.


**NOTE: ALL WOOD INTERIOR DOORS, UPPER & LOWER MOLDING & CROWN MOLDING TO BE STAINED W/ MINWAX #235 CHERRY AND POLYURETHANE W/ MINWAX FAST DRYING CLEAR SATIN.**  
**NOTE: F.R.P. SHOULD BE TO CEILING HEIGHT IN BACKROOM, BUT MUST BE A MINIMUM OF 8'-0" ABOVE FINISHED FLOOR. F.R.P. IN RESTROOMS MUST BE FLOOR TO CEILING.**

### TUSCANY II DECOR CALCULATIONS

**NOTE: THE SUBWAY STORE DESIGN DEPARTMENT WILL NOT ACCEPT RESPONSIBILITY FOR ANY INACCURACIES. THE CALCULATIONS PROVIDED BELOW MUST BE VERIFIED BY THE G.C. AND FRANCHISE OWNER BEFORE ANY ORDER FOR THESE MATERIALS IS ACCEPTED AND PLACED.**

QUANTITIES	CALCULATION WORKSHEET
1) 630 YARDS CITYSCAPE MURAL	1) M/TS + S/M + 10% DIVIDED BY 3.
2) 36 YARDS OF TUSCAN STUCCO WALL COVERING	2) M/TS + T/S + R/TS 10% DIVIDED BY 3
3) 91 FEET OF UPPER DECORATIVE MOLDING	3) M/TS + S/M + 10%
4) 107 FEET OF LOWER CHAIR RAIL MOLDING	4) M/TS + T/S + R/TS 10%
5) 11 YARDS OF GROUT WALL COVERING (ON-TELLAR) OR OPTIONAL BUTTERNUT BRICK WALLCOVERING ABOVE CITYSCAPE MURAL	5) (CEILING HEIGHT - 7'-6") X (M/TS + S/M + (Q/W/C DR B/T IN CUSTOMER AREA ONLY)) + 5% DIVIDED BY 12
6) 107' OPTIONAL HARDWOOD CROWN MOLDING (AT CORNER WHERE WALL AND CEILING MEET)	6) M/TS + S/M + R/TS (+ W/TS IF WINDOWS NOT TO CEILING) + 10%.
7) 107 FEET OF HARDWOOD CROWN MOLDING (FINISH CAP ON STRIP LIGHTING SHELF)	7) TOTAL LENGTH OF WALLS WHERE FLUORESCENT STRIP LIGHTING TO BE INSTALLED + 10%
8) 7 YARDS OF RED WALL COVERING	8) HEIGHT FROM TOP OF TUSCAN STUCCO WALL COVERING TO CEILING (36" AFF.) X R/TS + 5% DIVIDED BY 12
9) 11 YARDS OF GROUT WALLCOVERING (WITH TELLAR COATING) (FOR 48" HIGH BANQUETTE WALL ONLY)	9) Q/W/C + 10% DIVIDED BY 3. (CUSTOMER AREA ONLY)
10) 11 YARDS OF MARLITE F.R.P. ALMOND OPTIONAL (IF PERMITTED BY HEALTH/BUILDING CODE)	10) FP/L + 5% DIVIDED BY 12
11) 11 YARDS OF BUTTERNUT BRICK TEXTURED WALL COVERING	11) FP/L ON 8' HIGH WALLS X 2) + (FP/L ON 48" HIGH WALLS X 3) + 5% DIVIDED BY 12
12) 11 YARDS OF BUTTERNUT BRICK TEXTURED WALL COVERING	12) CEILING HEIGHT X R/T 5% DIVIDED BY 12
13) 11 YARDS OF GROUT WALL COVERING (WITH TELLAR COATING)	13) CEILING HEIGHT X Q/W/C + 5% DIVIDED BY 12
14) 0 RIGHT X LEFT VEGETABLE MOSAIC TILE	
15) 0 OPTIONAL FEET OF COPPER CORNICE TRIMS	
16) 0 4" X 12" SHEETS FOINT-HILL PEAR LAMINATE (OPTIONAL FOR SOFFIT APPLICATION)	16) TOTAL LENGTH OF CUSTOMER SIDE OF HEADERWALLS) OVER SERVICE AREA + 5%.
17) 9 MARLITE F.R.P. WHITE (ALMOND OPTIONAL (IF PERMITTED BY HEALTH/BUILDING CODE))	17) W/R + 5% DIVIDED BY 4
18) 9 PVC INSIDE CORNER	18) PANEL COUNT FROM #17 LESS 1
19) 4 PVC INSIDE CORNER	19) COUNT ALL INSIDE CORNERS WHERE W/R MEET
20) 0 PVC OUTSIDE CORNER	20) COUNT ALL OUTSIDE CORNERS WHERE W/R MEET
21) 6 PVC CAP MOLDING	21) COUNT ALL EDGES WHERE W/R BEGINS & ENDS & DOORWAYS.
22) 0 MARLITE F.R.P. ALMOND	22) A/FRP + 5% DIVIDED BY 4
23) 0 PVC DIVISION MOLDING	23) PANEL COUNT FROM #22/N/A. LESS 1
24) 0 PVC INSIDE CORNER	24) COUNT ALL INSIDE CORNERS WHERE A/FRP MEET
25) 0 PVC OUTSIDE CORNER	25) COUNT ALL OUTSIDE CORNERS WHERE A/FRP MEET
26) 0 PVC CAP MOLDING	26) COUNT ALL EDGES WHERE A/FRP BEGINS & ENDS & DOORWAYS.
27) 0 YARDS OF TUSCAN STUCCO IN RESTROOMS	27) HEIGHT FROM TOP OF WALL TILE TO CEILING (48"-52" AFF.) X RR/2 + 5% DIVIDED BY 8.
28) 0 YARDS OF TUSCAN STUCCO IN RESTROOMS	28) HEIGHT FROM TOP OF WALL TILE TO CEILING (48"-52" AFF.) X RR/2 + 5% DIVIDED BY 8.

**NOTE: THESE CALCULATIONS DO NOT INCLUDE THE MATERIALS NEEDED TO DECOR THE AREA ABOVE OR BELOW THE WINDOWS.**



**4 FLOOR & WALL FINISH PLAN**  
SCALE: 1/4" = 1'

### GENERAL NOTES:

- CEILING HEIGHT IS 9'
- ELECTRICAL OUTLET HEIGHTS MEASURED TO BOTTOM OF BOX.
- ONE ELECTRICAL JUNCTION BOX TO BE LOCATED IN CEILING ABOVE EACH WINDOW.
- CUND MODEL SV9-PLUS WATER FILTRATION SYSTEM IS REQUIRED IN ALL NEW STORES THAT DISPENSE BEVERAGES. THE RECOMMENDED PLACEMENT FOR INSTALLATION IS MOUNTED TO SODA SYRUP RACK BY COCA-COLA. SECONDARY PLACEMENT OPTION IS MOUNTED ON THE BACKROOM WALL. THIRD INSTALLATION OPTION IS MOUNTING INSIDE THE FRONT BEVERAGE COUNTER WHEN SPACE LIMITATIONS OCCUR. REQUIRED 1/2" INCOMING WATER LINE FEED WITH 1/2" BALL VALVE SHUTOFF AND 1/2" FPT CONNECTION. MINIMUM 110 VOLT, 20 AMP ELECTRICAL SERVICE TO SUPPORT THE CARBONATOR AND WATER BOOSTER (MUST BE DEDICATED CIRCUIT).
- SMARTCURVE STAND (OFR. DISPLAY-BOX) REQUIRED IN CUSTOMER AREA AT POINT OF ORDER (PREFERRED PLACEMENT).
- 21 3/4" X 13 1/8" BASE, 56" (WITHOUT HEADER) OVERALL HEIGHT. SECONDARY CHIP RACK IS REQUIRED IN THE CUSTOMER AREA. THE TWO AVAILABLE OPTIONS ARE BASKET STYLE CHIP RACK AT THE POINT OF ORDER (PREFERRED PLACEMENT) OR PURSE RAIL MOUNTED CHIP RACK (MOUNTED ON TOP OF THE PURSE RAIL).
- EXIT LIGHTS INSTALLED BY G.C. PER LOCAL CODE.
- EMERGENCY LIGHTS INSTALLED BY G.C. PER LOCAL CODE.
- EXTINGUISHERS, SMOKE AND FIRE DETECTION SYSTEMS INSTALLED BY G.C. PER LOCAL CODE.
- LABOR & MATERIAL SUPPLIED BY G.C. UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS TO BE VERIFIED BY G.C. ON SITE.
- DECOR SPECIFICATIONS ARE TO BE SUBWAY'S "TUSCANY II" SCHEME.

**SYMBOL LEGEND**

- - PHONE JACK
- - 120V DUPLEX OUTLET
- - 220V SINGLE OUTLET
- - JUNCTION BOX

**NOTES:**  
COVE BASE MATERIAL IS TO BE PROVIDED IN ALL AREAS WITH A 3/8" RADIUS COVE.  
RUBBER TOPSET IS NOT AN ACCEPTABLE MATERIAL IN FOOD PREP SERVICE AREAS.

REVISION: BY DATE

STORE MUST BE CONSTRUCTED AS DESIGNED IN THESE FLOOR PLANS SUBJECT TO FEDERAL, STATE AND LOCAL LAWS. RECIPIENT IS RESPONSIBLE FOR ENSURING COMPLIANCE WITH ALL LAWS. IF MODIFICATIONS ARE NECESSARY, PLEASE CONTACT DADS STORE DESIGN DEPARTMENT FOR WRITTEN APPROVAL OF THE REQUIRED CHANGES.

THIS DRAWING IS FURNISHED BY DOCTORS ASSOCIATES INC. (DAD) DBA SUBWAY. RECIPIENT MUST DETERMINE IF THIS DRAWING MUST BE SUBMITTED TO A LICENSED ARCHITECT OR SIMILAR PROFESSIONAL UNDER FEDERAL, STATE OR LOCAL LAW. ANY CHANGES MUST BE APPROVED BY DAD.

DO NOT SCALE DRAWING. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS AND SHALL BE VERIFIED IN THE FIELD BY THE GENERAL CONTRACTOR AND/OR FRANCHISEE/OWNER. ANY DISCREPANCY IN DIMENSIONS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF DADS AREA DEVELOPMENT AGENT OR DESIGNATED FIELD REPRESENTATIVE.

THE GENERAL CONTRACTOR AND EACH SUB-CONTRACTOR SHALL MAKE HIS OWN INSPECTIONS AND MEASUREMENTS ON AND SUBWAY SHALL NOT BE HELD RESPONSIBLE FOR THE ACCURACY OF DIMENSIONS AND FOR ERRORS AND OMISSIONS IN THE DRAWINGS IF WRITTEN CONFIRMATION HAS NOT BEEN RECEIVED BY DADS STORE DESIGN DEPARTMENT.

THIS DRAWING AND THE INFORMATIONAL CONTENT HERE OF IS THE CONFIDENTIAL PROPERTY OF DAD AND IS PROVIDED SOLELY FOR THE USE OF AUTHORIZED FRANCHISEES. THEIR AGENTS AND CONTRACTORS. RECIPIENT AGREES NOT TO REPRODUCE, COPY, USE OR TRANSMIT THIS DRAWING AND/OR ITS INFORMATIONAL CONTENT, IN WHOLE OR IN PART, OR TO ALLOW SUCH ACTION BY OTHERS, FOR ANY PURPOSE, EXCEPT WITH THE WRITTEN PERMISSION OF DAD. ACTING FOR SUBWAY, RECIPIENT FURTHER AGREES TO SURRENDER THIS DRAWING AND ANY PERMITTED COPIES HEREOF UPON DEMAND.

**FRANCHISEE:** MARWAHA  
**SUITE B**  
**DEVELOPMENT AGENT:** MARWAHA

8960 FLETCHER PKWY  
LA MESA, CA 91942

325 BIC DRIVE  
MILFORD, CT 06461

(203) 877-4281  
(800) 888-4848

DATE: JULY 8, 2010  
DESIGNED BY: DAVE MILLER  
DRAWN BY: D.G.M.  
REVIEWED BY:

SCALE: 1/4" = 1'-0"

SHEET #:  
2 OF 2  
PRINTED: 10/8/2010

©2008 DOCTORS ASSOCIATES, INC.