


NO.	DATE

**SUBWAY  
 SUITE B**  
 8960 FLETCHER PKWY  
 LA MESA, CA 91942



**PARKING**

55,000/250 = 220  
 238 SPACES PROVIDED

**ZONING**

C-G-D  
**A.P.N.**  
 4902104600

**LEGAL DESCRIPTION**

CITY: LA MESA 1.23  
 AC M/L IN LOT 2 SEC 17-16-1W  
 CITY/MUNI/TWP: LA MESA

**SITE PLAN NOTES**

- NO WORK PROPOSED IN THE PUBLIC RIGHT OF WAY AS PART OF THIS BUILDING PERMIT APPLICATION.
- IT SHALL BE THE RESPONSIBILITY OF THE APPLICANT TO LOCATE PROPERTY LINES AND CONFORM TO SET BACK REQUIREMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP OF ALL SILT AND MUD ON ADJACENT STREETS DUE TO THE CONSTRUCTION VEHICLES OR ANY OTHER CONSTRUCTION ACTIVITY, AT THE END OF EACH WORKDAY OR AFTER A STORM EVENT THAT CAUSES A BREACH IN INSTALLED CONSTRUCTION BMP'S, WHICH MAY COMPROMISE STORM WATER QUALITY WITHIN ANY STREET. A STABILIZED CONSTRUCTION EXIT MAY BE REQUIRED TO PREVENT CONSTRUCTION VEHICLES OR EQUIPMENT FROM TRACKING MUD OR SILT INTO THE STREET.
- ALL STOCKPILES OF SOIL AND OR BUILDING MATERIALS THAT ARE INTENDED TO BE LEFT FOR A PERIOD GREATER THAN SEVEN CALENDAR DAYS ARE TO BE COVERED. ALL REMOVABLE BMP DEVICES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE FIVE-DAY RAIN PROBABILITY FORECAST EXCEEDS 40%.
- A CONCRETE WASHOUT SHALL BE PROVIDED ON ALL PROJECTS, WHICH PROPOSE THE CONSTRUCTION OF ANY CONCRETE IMPROVEMENTS THAT ARE TO BE POURED IN PLACE ON SITE.
- THE CONTRACTOR SHALL RESTORE ALL EROSION/SEDIMENT CONTROL DEVICES TO WORKING ORDER AFTER EACH RUN-OFF PRODUCING RAINFALL OR AFTER ANY MATERIAL BREACHES ITS EFFECTIVENESS.
- ALL SLOPES THAT ARE CREATED OR DISTURBED BY CONSTRUCTION ACTIVITY MUST BE PROTECTED AGAINST EROSION AND SEDIMENT TRANSPORT AT ALL TIMES.
- THE STORAGE OF ALL CONSTRUCTION MATERIAL AND EQUIPMENT MUST BE PROTECTED AGAINST ANY POTENTIAL RELEASE OF POLLUTANTS INTO THE ENVIRONMENT.
- ALL SIGNS TO BE ISSUED UNDER SEPERATE PERMIT.
- PREVIOUS USE WAS "B" OCCUPANCY
- PLAN CHANGES DURING CONSTRUCTION REQUIRE PRIOR APPROVAL. PLEASE CONTACT BUILDING DEVISION AT (619) 667-1176 PRIOR TO DEVIATING FROM THE APPROVED PLANS

DWG. BY	J.P.
CHK'D BY	
DATE	7/30/2010
JOB NO.	6180
FILE NO.	619022

EXP. 12/31/10

**SHEET**  
**SITE**

PRINTED: 10/8/2010

PRINTED 9/21/2010