

NOTE:
TOP PLATE SPLICE:
4'-0" MIN. USE 16-16d COMM. NAILS
EACH SIDE OF BREAK OF UPPER PLATE
SEE DETAIL 8 SHEET D-3


FOR MISSING/MISPLACED STHD14 OR PHD5:
USE SIMPSON PHD5 AND RFB#5 x 15 W/
12" EMBEDMENT. USE SIMPSON SET EPOXY.
SPECIAL INSPECTION REQUIRED.

NOTE:
THE ELECTRICAL PANEL MAY NOT BE
LOCATED WITHIN A SHEARWALL
CONTRACTOR TO VERIFY ALL SHEARWALL
LENGTHS PRIOR TO CONSTRUCTION & VERIFY
ALL DOOR & WINDOW LOCATIONS
ACCORDINGLY. NOTIFY ENGINEER OF RECORD
OF ANY DISCREPANCIES PRIOR TO
CONSTRUCTION

*QA/QC=QUALITY CONTROL
INSPECTION REQ'D IF QA/QC NOTED

THE CONTRACTOR SHALL RETAIN THE ENGINEER OF RECORD TO
REVIEW & PROVIDE QUALITY CONTROL FOR ALL SHEAR
TRANSFER SYSTEMS REQUIRING NAILING AT 4" O.C. OR LESS I.E.
SHEARWALL "H" THIS PLAN. A REPORT SHALL BE SUBMITTED
TO THE BUILDING OFFICIAL FOR REVIEW & APPROVAL PRIOR TO
FRAMING INSPECTION APPROVAL.

IF QUALITY CONTROL IS NOT PROVIDED DURING THE COURSE OF
CONSTRUCTION, AS REQUIRED IN THESE PLANS, THERE WILL BE
A \$5000 BASE FEE PLUS TIME & MATERIALS AS REQUIRED FOR
TESTING & INSPECTIONS.



**PASQUINI
ENGINEERING**
INCORPORATED

903 H Street Suite 300
Bakersfield, CA 93304


Telephone: (805) 328-9600
Fax: (805) 328-9050

NO.	DATE

DIANE MIRONOWSKI
OFFICE/ WAREHOUSE
6107 WOODMERE DR.
BAKERSFIELD, CA.

THESE PLANS ARE NOT
FOR CONSTRUCTION
UNLESS A "WET STAMP &
SIGNATURE" FROM BOTH
THE ENGINEER OF RECORD
AND A APPROVAL STAMP
WITH A "WET STAMP &
SIGNATURE" FROM THE
LOCAL GOVERNING
AGENCY ARE PRESENT.

DWG. BY	L.H.
CHK'D BY	
DATE	2-13-12
JOB NO.	6510
FILE NO.	651022



SHEET
S-4
OF SHEET